# BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

**Executive Engineeer**
**Byatarayanapura Division**
**B.B.M.P., Bangalore - 92**

## DRAFT TENDER SCHEDULE

**Issued to :**

**Original / Duplicate**

**Name of Work: Maintenance of Existing Borewells in ward no. 07 Thanisandra Surrounding area.**

| Sl. No. | Quantity. | Description | Unit | Rates | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 1 | 70.00 | The lifting of submergible pumpset from well. | Each | 1500.00 | Rupees One Thousand Five Hundred Only |
| 2 | 35.00 | The Transportation of pumping machineries | Each | 1200.00 | Rupees One Thousand Two Hundred Only |
| 3 | 5.00 | Rewinding of submergible pumpset with copper winding wires of appropriate guage, as per specifications and / or directions of the departmental officials, including all materials, labour, equipment and testing. for all types of submergible pumpsets etc.(with guarantee period not less than 6 months) Above 7.5 HP to up to 8.0 HP | Each | 4019.00 | Rupees Four Thousand Nineteen Only |
| 4 | 5.00 | For all types of submersible pumpsets above 10 HP and upto 11 H.P. | Each | 5157.00 | Rupees Five Thousand One Hundred Fifty Seven Only |
| 5 | 10.00 | For all types of submersible pumpsets above 12 HP and upto 13 H.P | Each | 5983.00 | Rupees Five Thousand Nine Hundred Eighty Three Only |
| 6 | 15.00 | For all types of submersible pumpsets 15HP to 20 HP | Each | 8930.00 | Rupees Eight Thousand Nine Hundred Thirty Only |
| 7 | 25.00 | Pump bowls of same type and make | No. | 1500.00 | Rupees One Thousand Five Hundred Only |
| 8 | 25.00 | Intermediate Piece (I.P) With IP Leaded Bronxe bush | No. | 1050.00 | Rupees One Thousand Fifty Only |
| 9 | 35.00 | Upper Flange | No. | 650.00 | Rupees Six Hundred Fifty Only |
| 10 | 35.00 | lower Flange | No. | 650.00 | Rupees Six Hundred Fifty Only |
| 11 | 35.00 | Upper/ Lower Housing | No. | 1200.00 | Rupees One Thousand Two Hundred Only |
| 12 | 35.00 | Guide vane | No. | 700.00 | Rupees Seven Hundred Only |

| Sl. No. | Quantity. | Description | Unit | Rates | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 13 | 35.00 | Impeller Shell moulded with aluminium Bronze | No. | 1500.00 | Rupees One Thousand Five Hundred Only |
| 14 | 35.00 | Discharge outlet (D.O) Bearing D.O Steel Bush | No. | 2050.00 | Rupees Two Thousand Fifty Only |
| 15 | 10.00 | Pump shaft made out of stainless steel Centreless ground with key way (upto 8 stages) | No. | 1500.00 | Rupees One Thousand Five Hundred Only |
| 16 | 20.00 | Pump Coupling (Stainless Steel) | No. | 1500.00 | Rupees One Thousand Five Hundred Only |
| 17 | 40.00 | Stud and Nuts | Each | 200.00 | Rupees Two Hundred Only |
| 18 | 35.00 | Motor Base With Pin | Each | 500.00 | Rupees Five Hundred Only |
| 19 | 20.00 | The Starter of Motor up to 4 to 5 HP | No. | 3500.00 | Rupees Three Thousand Five Hundred Only |
| 20 | 20.00 | The Rotor of Motor up to 4 to 5 HP | No. | 2000.00 | Rupees Two Thousand Only |
| 21 | 35.00 | Carbon Housing | No. | 2000.00 | Rupees Two Thousand Only |
| 22 | 35.00 | The Carbon Housing (Thrust bearing block assembly complete with segment bearing pad). | No. | 2200.00 | Rupees Two Thousand Two Hundred Only |
| 23 | 30.00 | Oil Seal | No. | 350.00 | Rupees Three Hundred Fifty Only |
| 24 | 30.00 | Oil Seal Steel Bush | No. | 250.00 | Rupees Two Hundred Fifty Only |
| 25 | 35.00 | Steel bearing Bush | No. | 400.00 | Rupees Four Hundred Only |
| 26 | 40.00 | Allen Screw | No. | 1200.00 | Rupees One Thousand Two Hundred Only |
| 27 | 35.00 | Pump Key (Stainless Steel) | No. | 650.00 | Rupees Six Hundred Fifty Only |
| 28 | 10.00 | Non – return valve (NRV) assembly complete with rubber 'O' Ring | No. | 650.00 | Rupees Six Hundred Fifty Only |
| 29 | 25.00 | Cable Guard | No. | 350.00 | Rupees Three Hundred Fifty Only |
| 30 | 25.00 | Strainer | No. | 450.00 | Rupees Four Hundred Fifty Only |
| 31 | 30.00 | Brass Filter | No. | 1050.00 | Rupees One Thousand Fifty Only |
| 32 | 30.00 | Lock Ring | Each | 350.00 | Rupees Three Hundred Fifty Only |
| 33 | 30.00 | The Carbon Housing (Top carbond / ferrodo padding) | Each | 350.00 | Rupees Three Hundred Fifty Only |

| Sl. No. | Quantity. | Description | Unit | Rates | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 34 | 35.00 | Bearing (Gunmetal) Centrifugal) Cast Aluminium Bronxe, Beaing bush | Each | 850.00 | Rupees Eight Hundred Fifty Only |
| 35 | 35.00 | Circillps | Each | 200.00 | Rupees Two Hundred Only |
| 36 | 56.70 | Earth work excavation for pipeline trenches in all kinds of soils by mechanical means as per drawing and technical specifications, including setting out, construction of shoring, strutting, barricading, caution lights, bracing, using sight rails & bonding rods at every 100 mm wherever necessary as directed, removal of stumps and other deleterious matter, dressing of sides and levelling the bottom of trench to the extent required , utilising the available excavated earth locally for the work etc., and all other appurtenances complete in the following strata. All kinds of soils. Depth upto 1.50 m | Cum | 288.20 | Rupees Two Hundred Eighty Eight and Twenty Paise Only |
| 37 | 210.00 | Providing and installing at site of work P.V.C. pipes including cost of pipes and specials and labour, including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour charges and all lift charges, handling charges including encasing the pipe around to a depth not less than 15 cms with gravel or selected earth available from the excavation etc. complete.75mm (weight of pipe - 0.917 kg) | Mtr | 226.60 | Rupees Two Hundred Twenty Six and Sixty Paise Only |
| 38 | 56.70 | Refilling available earth around trenches/pipelines, cables in layers not exceeding 20 cms in depth, compacting each deposited layer by ramming after watering with a lead upto 50 m , and lift upto 1.5 m. Including cost of all labour complete as per specifications | Cum | 164.80 | Rupees One Hundred Sixty Four and Eighty Paise Only |
| 39 | 600.00 | Supply of Drinking Water through water tankers of Capacity 5000 Liters Hiring of Water Tanker.<br>Hire Charges of Tractor 40 HP including Operator and Fuel.<br>Procurement of Water.<br>Providing causal labours (unskilled mazdoor heavy). | Per Load | 576.00 | Rupees Five Hundred Seventy Six Only |

ಸದರಿ ಕೆಲಸಕ್ಕೆ ಸಲ್ಲಿಸಿರುವ
ಕಿಡ್ಡುಪಡಿಗಳ ಸಂಖ್ಯೆ.....( )
ಕಿಡ್ಡುಪಡಿ ಮಾಡಿ/ಇಲ್ಲದೆ
ಅನುಮೋದನೆ ನೀಡಿರಾಗಿದೆ

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ
ಬ್ರ.ಬೆ.ಮ.ಪಾ., ಬೆಂಗಳೂರು

**Executive Engineer**
ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
**Byatarayanapura Division**
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ
**BBMP, Bangalore - 92**
ಬ್ರ.ಬೆ.ಮ.ಪಾ., ಬೆಂಗಳೂರು

**Note:**

1 Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)

2 Unit rates and prices shall be quoted by the Tender in Indian rupees.

3 Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)

4 Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))